ENGINEERING DEPARTMENT.

GOVERNMENT OF MYSORE, ELECTRICAL DEPARTMENT.

Notice dated 20th January 1925.

Notice is hereby given that sealed tenders will be received at the office of the Chief Electrical Engineer, Bangalore, up to the 7th February 1925, for extending the Chief Electrical Engineer's Office building. The tenders will be opened in public at 12 noon on Saturday the 7th February 1925. The work should be completed within three months from the date of acceptance of the tender.

2. The plans, detailed estimates and conditions may be obtained at the office of the undersigned, between the hours of 11 A.M. and 5 P.M., on any working day.

3. Tenders should be submitted in the usual form and should be accompanied by a statement in the form given below showing the rates at which different items specified will be executed.

4. The final acceptance of the tender will rest with the Chief Electrical Engineer who is not bound to accept the lowest or any tender or assign any reason whatever for the rejection of any tender.

5. Each tender must be accompanied with an earnest money of rupees two hundred (Rs. 200) in cash or Government Promissory Note and be superscribed "Tender for extending the Chief Electrical Engineer's Office building at Bangalore," in default of which, tenders will be rejected.

6. Within five days from the award of tender, the successful tenderer will be required to execute the usual contract bond, in default of which, his tender will be considered as cancelled, and the earnest money forfeited.

7. The name of the successful tenderer will be posted in the office of the Chief Electrical Engineer to the Government of Mysore, Bangalore, in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of any of the tenders, the earnest money on rejected tenders will be returned.

9. The construction work should be started within ten days from the notification of acceptance of tender.

Statement showing the approximate quantities of work for extending the Chief Electrical Engineer's office building at Bangalore.

No.	Items of work	Per	Quantity
1	Earthwork excavation	C. yd.	19
2	Earth filling in basement	,,	26
3	Chunam concrete foundation	C. ft.	200
4	Stone in chunam mortar, foundation and basement	,,	577
5	Do do superstructure, courses to tally with the existing building	,,	962
6	Stone slabs 6" thick exposed parts nicely dressed	Sq. ft.	59
7	Chunam plastering two coats	Sqr.	11·78
8	Calcarium distemper washing two coats	,,	14·83
9	Do do work	R. ft.	101
10	Chunam pointing	Sqr.	2·70
11	Encaustic, flooring tiles on 3" concrete and cement points	,,	8·33
12	Rolled steel I—Beams fixed complete	Cwt.	46·88
13	Teakwood glazed windows as per detailed drawing	Sq. ft.	120
14	Madras terrace roofing 9" thick complete	Sqr.	8·84
15	Teakwood wrought and put up with wood oiling	C ft.	111·74
16	Brick in mortar, cornice 9" projection	R. ft.	29
17	Do parapet wall ordinary	,,	29
18	Painting with 3" coats of silicate paint	Sqr.	4·14
19	Inserting bond stones in joining old and new masonry	L. S.	1 item
20	Galvanized iron rain water down pipes 4½" dia.	R. ft.	20
21	Dismantling verandah room including roofing, wood work, flooring, drains, etc., complete.	L. S.	1 item
22	Re-arranging Mangalore tiled roofs after the new building is built	,,	,,
23	Stone slabs 4" thick exposed parts nicely dressed	Sq. ft.	48
24	Stone brackets 6" thick 21" × 14" fixed complete	Each	6
25	Old Cuddapah slabs set in mortar and cement pointed	Sq. ft.	11
26	Constructing drain with old Cuddapah slabs with chunam and cement plastering	R. ft.	29
27	Putting chunam concrete 3" thick and cement plaster on top	Sqr	0·29

B. D. NATH.
For *Chief Electrical Engineer.*